

Cleanroom Construction

Modular Approaches


8

Sequence of Construction



Meeting Agenda

- Traditional vs Modular Decision
- Which Approach?
- Modular Systems Available
- Construction Approaches





Traditional vs. Modern

- Traditional (Stud & Gyp):
 - Labor available & economical
 - Finish craftsmen quality known
 - Schedule not a driving force
 - Retrofit to match existing
 - "Material" cost vs. delivered cost
 - Epoxy paint most reliable
 - Capital vs. lease hold improvement



Traditional vs Modular Concepts

- Widely held belief that a prefabricated
- approach to construction is more
- expensive
- Once was the case but gap is narrowing to favour modular pre-fabricated solutions:
 - Manufacturing economies of scale
 - Increased site Labour costs
 - Increasing Health & Safety demands



Traditional Vs. Modular

- Modular (Walls and Ceilings):
 - Site labor reduced ~70%
 - Precise manufactured tolerances
 - Cleaner "clean build" construction
 - cGMP details & finishes available
 - Deliver system later in the program
 - Depreciation schedule vs. building
 - Future flexibility / expandability
 - Reduced commissioning/validation exposure
 - Robust systems







12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Robust: Modular / Skid Integration





Modular: Now Which Approach?


- Modular Building
- Modular Systems


12512 LAKESTONE DR MIDLOTHIAN, VA 23114 804-678-9888

Modular 3D Modeling













12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Modular Building





Modular Systems

- Modular walls / ceilings
- Traditional building services
 - Process systems
 - Mechanical equipment decks
 - Sequence of construction



Modular Systems

- "Butler" steel buildings
- Process skids
- Prefabricated mezzanines
- Pipe racks
- Prefabricated support rooms (switch gear, teledata)
- cGMP Envelopes



US Case Study

- Unistrut from building steel or intermediate steel
- Panelized walkable ceiling
- Simultaneous construction
 - High level work (duct, fire etc)
 - Epoxy floors
- Walls/Super Skids Integration



CCA

12512 LAKESTONE DR MIDLOTHIAN, VA 23114

US Case Study





US Case Study



12512 lakestone dr Midlothian, va 23114





Ireland Case Study

- Design Features
 - Platform ceiling
 - Hollow core walls
- Integrated
 - Lights/ Filters
 - M&E Services distribution
- Benefits
 - Parallel construction
 - Ease of maintenance access, (wide hangers)
 - No trip hazards
 - Interchangeability



Ireland Case Study



12512 LAKESTONE DR MIDLOTHIAN, VA 23114





cGMP Envelope Manufacturers

- Plascore
- MSS (AES)
- Clestra
- Dagard
- Daldrop



Plascore

- Based in USA
- Leader in Aluminum honeycomb core
- Pharma Product Line
 - Aluminum honeycomb core
 - uPVC finish
 - Wall/ceiling panels with internal frame
 - 5'x10' and 4'x10' Ceiling panels
 - Door/hardware solutions
 - 2", Liner, Cavity wall options
 - Framed wall option



MSS (AES)

- Based in USA = AES
- Based in England = MSS
- First to market in US
- English MSS has installations in Ireland
- Product Line
 - Aluminum honeycomb core only
 - uPVC finish only
 - Panels not framed
 - Ceiling panel/tray support system
 - Progressive wall system



Dagard

- French, (cold rooms and cleanrooms)
- Significant presence in Pharma
- Product Line
 - Choice of panel cores
 - Choice of finishes (uPVC, epoxy)
 - Integrated ceilings (lights, filters etc)
 - Progressive wall system
- Significant installations in Ireland



Clestra

- French plants in France, India & Korea
- In Pharma since mid 70s
- Global capacity & capability
- Product Line GMP variety & choice
 - Panel cores & finishes
 - Load bearing, interchangeable & platform ceilings
 - Fully non-progressive
- In Ireland since early 90s





Daldrop

- German
- Specialist HVAC Engineering Company
- Turnkey provider
- Own product range, (Pharma & Micro)
- Product Line
 - Panel cores & finishes
 - Load bearing, interchangeable split panel ceiling system
 - Fully non-progressive
- Large projects in Ireland



Construction Approaches


Interactive Conversation





12512 LAKESTONE DR MIDLOTHIAN, VA 23114


Bay Framing Unistrut Secondary with GP or Panel Ceiling



JACOBS



Bay Frame with Beam Non-Integrated Ceiling




JACOBS



12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Bay Framing with Tube Walkable Ceiling



OPTION C — BAY FRAMING WITH TUBE SECONDARY FRAMING & WALKABLE CEILING

SCALE: NTS 10 MAY, 2008


JACOBS





12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Bay Framing with Unistrut





CCA

12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Poor Interstitial Space Management





CCA

12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Better Interstitial Space Management





12512 LAKESTONE DR MIDLOTHIAN, VA 23114

Optimal Interstitial Space Management





Schedule Review

Review schedule & discuss sequence of construction





Whiteboard Discussions

- Construction
- Schedule

12512 LAKESTONE DR MIDLOTHIAN, VA 23114 804-578-9888